



PLAN NOTES

- ① PROVIDE BUTTERFLY VALVES IN LIEU OF BALL VALVES WHEN PIPE SIZES ARE ABOVE 2", (TYPICAL).
- ② INSTALL AT LOWEST POINT IN PIPING.
- ③ INSTALL MODULATING VALVE SO THAT STEM IS VERTICAL.
- ④ THERMOMETERS TO BE PROVIDED ONLY FOR AHU COILS.


2-WAY WATER COIL PIPING DETAIL
 NO SCALE