



## **PLAN NOTES**

- 1 PROVIDE BUTTERFLY VALVES IN LIEU OF BALL VALVES WHEN PIPE SIZES ARE ABOVE 2". (TYPICAL)
- (2) INSTALL AT LOWEST POINT IN PIPING.
- (3) INSTALL MODULATING VALVE SO THAT STEM IS VERTICAL.
- 4 REFER TO PLANS AND SCHEDULES FOR QUANTITY OF COILS IN COIL BANK. EACH COIL TO BE PIPED SEPARATELY AS SHOWN.
- (5) THERMOMETERS TO BE PROVIDED ONLY FOR AHU COILS.

